

June 10, 2019

Courtney Rizzo
Principal
Farb Middle School
4880 La Cuenta Drive
San Diego, CA 92124

Subject: Farb MS Drinking Water Project Closeout

Dear Mrs. Rizzo:

The following information is provided as a project closeout report for the recent drinking water lead remediation work at the Farb Middle School campus.

As part of a Districtwide effort the Physical Plant Operations (PPO) staff began testing all drinking water outlets at Farb MS for elevated levels of lead. PPO staff first identified all drinking water outlets and tagged them with a blue label. Safety Office staff then collected water samples from each drinking water outlet and delivered the samples to a state certified laboratory for analysis. The federal EPA standard for lead in drinking water is 15 parts per billion (ppb); however, the district standard is much more stringent at 5 ppb. Drinking water fixtures that measured above the district standard were tagged "out of service" while remedial actions took place.

The attached report shows that some drinking water fixtures required remedial action in order to meet the district's strict standard of 5 ppb. Once the remedial action was completed, a re-test was conducted to confirm the remedial action was successful. All site repairs are now complete, please see the attached sampling log for more information. This project is considered closed.

Now that all drinking water outlets on the Farb MS campus meet the district's lead standard of 5 ppb, your campus is now cleared from the district's daily water flushing requirement. Instead, please instruct staff to flush all drinking water outlets marked with a blue sticker for one minute in the morning of the first day of school each week, rather than every morning. Please let me know if you have any questions.

Sincerely,

Steven J. Ditto
Manager, Facilities Planning



SAN DIEGO UNIFIED SCHOOL DISTRICT DRINKING WATER SAMPLING REPORT

Facility: Farb MS

Report Type: Closeout Report

Date of Report: 06/10/19

Location	DWO No	Type	Initial Result*	Action Taken**	Clearance Result
1 Admin/Kitchen/Library/Supply - Farb_01-01 First Aid Office, South Wall	DWO-367-001	Faucet	0.87	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Office Workroom 1, South Wall	DWO-367-002	Faucet	1.61	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Building Exterior, East Wall	DWO-367-003	Drinking Fountain Bubblers	0.45	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Building Exterior, East Wall	DWO-367-004	Drinking Fountain Bubblers	0.61	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Library Workroom 2, East Wall	DWO-367-005	Faucet	0.64	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Kitchen, South Wall left	DWO-367-006	Faucet	3.97	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Building Exterior, West Wall	DWO-367-007	Drinking Fountain Bubblers	1.61	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Building Exterior, West Wall	DWO-367-008	Drinking Fountain Bubblers	<5	INIT	
1 Admin/Kitchen/Library/Supply - Farb_01-01 Building Exterior, West Wall	DWO-367-009	Drinking Fountain Bubblers	0.89	INIT	
2 Classrooms 21-26 - Farb_01-02 Classroom/Non-Standard - 21T, West Wall	DWO-367-010	Drinking Fountain Bubblers	5.37	FLTR	ND
2 Classrooms 21-26 - Farb_01-02 Classroom/Non-Standard - 23T, South Wall	DWO-367-011	Drinking Fountain Bubblers	2.15	INIT	
2 Classrooms 21-26 - Farb_01-02 Classroom/Non-Standard - 24T, South Wall	DWO-367-012	Drinking Fountain Bubblers	2.60	INIT	
2 Classrooms 21-26 - Farb_01-02 Classroom/Non-Standard - 26T, East Wall	DWO-367-013	Drinking Fountain Bubblers	1.59	INIT	
2 Classrooms 21-26 - Farb_01-02 Building Exterior, South Wall	DWO-367-014	Drinking Fountain Bubblers	2.58	INIT	
2 Classrooms 21-26 - Farb_01-02 Building Exterior, South Wall	DWO-367-015	Drinking Fountain Bubblers	3.42	INIT	
2 Classrooms 21-26 - Farb_01-02 Building Exterior, South Wall	DWO-367-016	Drinking Fountain Bubblers	4.06	INIT	



SAN DIEGO UNIFIED SCHOOL DISTRICT DRINKING WATER SAMPLING REPORT

Facility: Farb MS

Report Type: Closeout Report

Date of Report: 06/10/19

	Location	DWO No	Type	Initial Result*	Action Taken**	Clearance Result
17	3 Classrooms 31-36 - Farb_01-03 Building Exterior, South Wall	DWO-367-017	Drinking Fountain Bubblers	1.64	INIT	
18	3 Classrooms 31-36 - Farb_01-03 Building Exterior, South Wall	DWO-367-018	Drinking Fountain Bubblers	2.13	INIT	
19	3 Classrooms 31-36 - Farb_01-03 Building Exterior, South Wall	DWO-367-019	Drinking Fountain Bubblers	2.34	INIT	
20	3 Classrooms 31-36 - Farb_01-03 Classroom/Non-Standard - 31T, West Wall	DWO-367-020	Drinking Fountain Bubblers	5.27	FLTR	ND
21	3 Classrooms 31-36 - Farb_01-03 Classroom/Non-Standard - 33T, South Wall	DWO-367-021	Drinking Fountain Bubblers	2.04	INIT	
22	3 Classrooms 31-36 - Farb_01-03 Classroom/Non-Standard - 34T, South Wall	DWO-367-022	Drinking Fountain Bubblers	11.10	FLTR	ND
23	3 Classrooms 31-36 - Farb_01-03 Classroom/Non-Standard - 36T, East Wall	DWO-367-023	Drinking Fountain Bubblers	2.57	INIT	
24	4 Classrooms 41-46 - Farb_01-04 Classroom/Non-Standard - 41T, North Wall	DWO-367-024	Drinking Fountain Bubblers	3.17	INIT	
25	4 Classrooms 41-46 - Farb_01-04 Classroom/Non-Standard - 43T, West Wall	DWO-367-025	Drinking Fountain Bubblers	6.10	FLTR	ND
26	4 Classrooms 41-46 - Farb_01-04 Classroom/Non-Standard - 44T, West Wall	DWO-367-026	Drinking Fountain Bubblers	4.88	INIT	
27	4 Classrooms 41-46 - Farb_01-04 Classroom/Non-Standard - 46T, South Wall	DWO-367-027	Drinking Fountain Bubblers	4.14	INIT	
28	4 Classrooms 41-46 - Farb_01-04 Building Exterior, West Wall	DWO-367-028	Drinking Fountain Bubblers	<5	INIT	
29	4 Classrooms 41-46 - Farb_01-04 Building Exterior, West Wall	DWO-367-029	Drinking Fountain Bubblers	2.02	INIT	
30	4 Classrooms 41-46 - Farb_01-04 Building Exterior, West Wall	DWO-367-030	Drinking Fountain Bubblers	2.20	INIT	
31	5 Classrooms 51-56 - Farb_01-05 Building Exterior, West Wall	DWO-367-031	Drinking Fountain Bubblers	1.11	INIT	
32	5 Classrooms 51-56 - Farb_01-05 Building Exterior, West Wall	DWO-367-032	Drinking Fountain Bubblers	0.96	INIT	



SAN DIEGO UNIFIED SCHOOL DISTRICT DRINKING WATER SAMPLING REPORT

Facility: Farb MS

Report Type: Closeout Report

Date of Report: 06/10/19

	Location	DWO No	Type	Initial Result*	Action Taken**	Clearance Result
33	5 Classrooms 51-56 - Farb_01-05 Building Exterior, West Wall	DWO-367-033	Drinking Fountain Bubblers	<5	INIT	
34	5 Classrooms 51-56 - Farb_01-05 Classroom - 51T Ind Study, North Wall	DWO-367-034	Drinking Fountain Bubblers	5.35	FLTR	ND
35	5 Classrooms 51-56 - Farb_01-05 Classroom - 53T Ind Study, West Wall	DWO-367-035	Drinking Fountain Bubblers	4.99	INIT	
36	5 Classrooms 51-56 - Farb_01-05 Classroom - 54T Ind Study, West Wall	DWO-367-036	Drinking Fountain Bubblers	3.53	INIT	
37	5 Classrooms 51-56 - Farb_01-05 Classroom - 56T Ind Study, South Wall	DWO-367-037	Drinking Fountain Bubblers	15.50	FLTR	ND
38	Portable B08 - Farb Classroom - B08, West Wall	DWO-367-038	Drinking Fountain Bubblers	6.04	FLTR	ND
39	1 Admin/Kitchen/Library/Supply - Farb_01-01 Counseling Center, west wall of hallway, across from site	DWO-367-039	Drinking Fountain Bubblers	19.8	FLTR	ND
40	1 Admin/Kitchen/Library/Supply - Farb_01-01 Counseling Center, west wall of hallway, across from site	DWO-367-040	Drinking Fountain Bubblers	19.4	FLTR	ND
41	600 Multi-Purpose/Lockers/Science - Farb_02-06 Faculty Workroom - WRK1,	DWO-367-041	Faucet - Removed Prior to Testing	NA		
42	1 Admin/Kitchen/Library/Supply - Farb_01-01 Staff Kitchen, West Wall	DWO-367-042	Faucet	0.82	INIT	
43	1 Admin/Kitchen/Library/Supply - Farb_01-01 Kitchen, south wall, right	DWO-367-043	Spray Faucet	<5	INIT	

***Action levels and color indication**

Federal action level is above 15 ppb (parts per billion). SDUSD uses an action level that is stricter and includes anything above 5 ppb. Items indicated in green are below District action level. Items indicated in yellow are above District action level. Items indicated in red are above both District and Federal action levels. Green indicates no action needed. Red/Yellow indicates action needed.

****Clearance actions**

INIT=Initial result cleared no action needed. FLTR=Filter has been installed. PLMB=Plumbing work performed. RRC=Repeat and repeat-confirmation testing has been performed and both samples yielded results below District action level. RMOV=The drinking water outlet has been removed from service.